Preparing for your rewire

Please read this pack in full, then sign to confirm you understand before your installation is booked in.

A full rewire is major electrical work. To keep your installation on schedule, safe, and to the fixed price you were quoted, we need your home ready for our engineers on the first day. The points below explain what you need to do and what you should expect during the works.

1. Access & clearing the work areas

Before we arrive, please make sure every room in scope is ready for us to work in:

- **Loft spaces must be completely clear.** Remove all stored items, boxes and belongings so our engineers have full, safe access to run cables. Boarded lofts may need boards lifted.
- **Take down all wall-mounted items** — pictures, mirrors, frames, shelves, TVs and ornaments. Walls will be chased and cables run, and we cannot be responsible for items left in place.
- **Move furniture away from walls** where possible, or clear rooms entirely. We will move heavy items with care where needed, but clear rooms speed the work and reduce risk.
- Empty fragile or valuable items from cupboards, shelves and surfaces in the work areas.
- Please keep children and pets out of active work areas for their safety.

2. Floors, carpets & making good

- **Laminate and hard flooring must be lifted and re-laid by you.** We do not lift, remove or refit laminate, engineered wood, LVT, tiles or similar. Please arrange for any hard flooring in the work areas to be up before we arrive and re-laid afterwards. Areas that cannot be accessed because flooring is still down may not be able to be rewired.
- **Carpets are lifted for access only and not guaranteed to be re-laid as before.** Where we lift carpets to run cables we will refit them as carefully as we can, but old carpets, gripper rods and underlay can be damaged on lifting and may not return to their original finish. Replacement of floor coverings is not included in your quote.
- **Plastering and making good are not included.** A rewire involves chasing walls and lifting floorboards. We leave walls chased and first-fixed ready for a plasterer — we do not fill, skim, plaster or make good. Plastering, patching, painting, wallpapering and tiling are your responsibility and are not included unless separately quoted and agreed in writing.
- Some dust and disruption is unavoidable. We take reasonable steps to minimise mess, but a rewire is intrusive work.

3. On the day of your installation

- **Your rewire is completed in a single visit.** We carry out first fix and second fix on the same day — we do not first-fix and return weeks later. This means an intensive day's work, which is why having the property fully prepared matters.
- Your power will be off for periods during the works. Please plan around this, particularly for medical equipment, home working or deliveries.
- Please provide safe, clear access to the property and to the consumer unit / meter position for the full working day.
- Parking near the property for our van and materials is a great help where available.
- All work is carried out to **BS 7671** and certified. Any C1 or C2 issues found are made safe / rectified on the day.

Why we ask you to sign

This isn't about small print — it's so there are no surprises on the day and your fixed price stays fixed. If anything here is unclear, just ask your Ecco contact before you sign.

Customer declaration

I confirm that I have read and understood the "Preparing for your rewire" information above. In particular I understand that:

- Loft spaces and work areas must be cleared before the installation, and wall-mounted items removed;
- Laminate and hard flooring must be lifted and re-laid by me — Ecco does not lift or refit it, and areas left covered may not be rewired;
- Carpets are lifted for access only and not guaranteed to be re-laid as before, and floor-covering replacement is not included;
- Plastering and making good are not included — walls are left chased ready for my own plasterer;
- The rewire is carried out in a single day (first and second fix together), and the electrical supply will be interrupted during the works.

Customer name (print) _____ **Property address** _____

Signature _____ **Date** _____

Please sign and return this page to your Ecco contact before your installation date. A signed copy will be kept with your job file.
Quote reference: _____